STORM DRAIN

SANITARY SEWER

SANITARY SEWER MANHOLE

SOLID WALL POLYETHYLENE PIPE

TYPICAL

TO BE REMOVED

WATER PAINT MARK

ALDER

CEDAR

COTT**(FNRW**OOD

HEMLOCK

HOLLY

SPRUCE

UNKNOWN

DESCRIPTION

WATER CAP

CONCRETE BLOCKING

BUTTERFLY VALVE

11' BEND

45' BEND

90' BEND

22' BEND

VALVE

HYDRANT ASSEMBLY

BLOW-OFF VALVE

REDUCER

AIR-VAC ASSEMBLY

WATER METER

PROPOSED WATER SYMBOLS

WATER VALVE WATER METER IRRIGATION CONTROL VALVE GAS VALVE GUY ANCHOR UTILITY/POWER POLE POWER VAULT POWER TRANSFORMER SANITARY SEWER MANHOLE

FIRE HYDRANT

CONIFEROUS TREE METAL FENCING GAS PAINT MARK WATER PAINT MARK TELEPHONE PAINT MARK

UNDERGROUND POWER ———UG——— STORM SYMBOLS DESCRIPTION

TYPE 1 CATCH BASIN, GRATED LID TYPE 1 CATCH BASIN, SOLID LID TYPE 2 CATCH BASIN, GRATED LID TYPE 2 CATCH BASIN, SOLID LID BEEHIVE MANHOLE COVER SQUARE YARD DRAIN ROUND YARD DRAIN

STORM PIPE PROPOSED SEWER SYMBOLS SYMBOL DESCRIPTION SEWER CAP SEWER CLEANOUT

STORM CLEAN OUT

SEWER MANHOLE

SEWER PIPE

**CONTACT LIST** 

**APPLICANT:** DR HORTON - SEATTLE DIVISION 11241 SLATER AVE NE, SUITE 200 KIRKLAND, WASHINGTON 98033 CONTACT: JON BEEM PHONE: (425) 821-3400 ex. 5406 CELL: (425) 324-0572 EMAIL: jbeem@drhorton.com

SURVEYOR: LDC, INC.

20210 142ND AVE NE WOODINVILLE, WA 98072 CONTACT: VINCE TOWNSEND, PLS PHONE: (425) 806-1869 FAX: (425) 482-2893 EMAIL: vtownsend@ldccorp.com

ARBORIST:

CREATIVE LANDSCAPE SOLUTIONS 17518 NE 119TH WAY REDMOND, WASHINGTON 98052 CONTACT: SUSAN PRINCE PHONE: (425) 890-3808 EMAIL: sprince202@aol.com

TRAFFIC ENGINEER: KIMLEY-HORN 22722 29TH DR SE, SUITE 100 BOTHELL, WA 98021 CONTACT: BRAD LINCOLN, PE PHONE: (425) 708-8275 EMAIL: Brad.Lincoln@kimley-horn.com FAX: (425) 415-0311

CIVIL ENGINEER: LDC, INC.

20210 142ND AVE NE WOODINVILLE, WA 98072 CONTACT: TOM ABBOTT, PE PHONE: (425) 806-1869 FAX: (425) 482-2893 EMAIL: tabbott@ldccorp.com

LANDSCAPE ARCHITECT: CRAMER DESIGN CONSULTANTS, INC 1909 242ND ST SE BOTHELL, WASHINGTON 98012 CONTACT: GAYLE CRAMER PHONE: (425) 241-6258 EMAIL: cdclsa@frontier.com

WETLAND BIOLOGIST: ACRE ENVIRONMENTAL CONSULTING, LLC. 17715 28TH AVE NE LAKE FOREST PARK, WASHINGTON 98155

CONTACT: LOUIS EMENHISER


PHONE: (206) 450-7746

EMAIL: louis@acreenvironmental.com GEOTECHNICAL ENGINEER: THE RILEY GROUP, INC. 17522 BOTHELL WAY NE BOTHELL, WA 98011 CONTACT: KRISTINA WELLER, PE PHONE: (425) 415-0551

A PORTION OF THE N 1/2 OF THE NW 1/4 OF SEC 22, TWN 24 N, RGE 6 E, W.M., KING COUNTY, WASHINGTON

# PARKLAND HEIGHTS

PRELIMINARY PLAT



PROJECT INFORMATION

TAX PARCELS: 2224069039 SITE ADDRESS: 4929 ISSAQUAH-PINE LAKE RD SE ISSAQUAH, WA 98029 SITE AREA: 232,555 SF 5.34 AC **CURRENT ZONING:** SF-SL PROPOSED ZONING: SF-SL PROPOSED LAND USE: RESIDENTIAL PROPOSED LOTS: SAMMAMISH PLATEAU WATER WATER: SEWER: SAMMAMISH PLATEAU WATER POWER: PUGET SOUND ENERGY PUGET SOUND ENERGY **TELEPHONE:** COMCAST CABLE: COMCAST SCHOOL DISTRICT ISSAQUAH #411 FIRE DISTRICT: EASTSIDE FIRE REQUIRED MINIMUM SETBACKS: FRONT: REAR: SIDE:

FÓUND CONC. MON. W/ LEAD PLUG. (6-7-21)

PROJECT STANDARDS

NEIGHBORHOOD SUBAREA:

CARA DESIGNATION:

2014 DEPARTMENT OF ECOLOGY MANAGEMENT MANUAL FOR WESTERN WASHINGTON 2017 CITY OF ISSAQUAH STORMWATER DESIGN MANUAL ADDENDUM 2010 CITY OF ISSAQUAH STREET STANDARDS 2021 CITY OF ISSAQUAH STORMWATER STANDARDS NOTE: DEVELOPMENT TO BE SERVED BY SAMMAMISH PLATEAU WATER FOR SEWER AND WATER UTILITIES

NORTH ISSAQUAH

CLASS 3

# TABLE OF CONTENTS

2224069025

COVER SHEET (CS-01)

EXISTING CONDITIONS MAP (TO-01) TREE RETENTION PLAN (TR-01)

PRELIMINARY TESC, GRADING AND DRAINAGE PLAN (ER-01)


PRELIMINARY TESC NOTES AND DETAILS (ER-02)

PRELIMINARY SITE PLAN (SP-01)

PRELIMINARY ROAD PROFILES (RD-01 - RD-04)

PRELIMINARY ROAD SECTIONS (RD-05) NOTES AND DETAILS (DT-01)

MAILBOX APPROVAL PLAN LANDSCAPE PLANS E1.01 - E1.03 LIGHTING PLANS



# SURVEY INFORMATION

# LEGAL DESCRIPTION

QUIT CLAIM DEED RECORDING NO. 2015005000960

THE NORTHEAST QUARTER OF SECTION 22, TOWNSHIP 24, NORTH, RANGE 6 EAST, WILLAMETTE MERIDIAN, IN KING COUNTY, WASHINGTON, LYING WESTERLY OF THE SOUTHWESTERLY MARGIN OF VAUGHN HILL ROAD EXTENSION (ALSO KNOWN AS ISSAQUAH—PINE LAKE ROAD SOUTHEAST);EXCEPT THE NORTH 30 FEET THEREOF CONVEYED TO KING COUNTY FOR ROAD PURPOSES BY DEED RECORDED UNDER RECORDING NUMBER 2440235; AND EXCEPT THE PORTION CONVEYED TO THE CITY OF ISSAQUAH, STATE OF WASHINGTON FOR ROAD PURPOSES BY DEED RECORDED UNDER RECORDING NUMBER 201302150009

SITUATE IN THE COUNTY OF KING, STATE OF WASHINGTON.

#### HORIZONTAL DATUM

WASHINGTON STATE COORDINATES-NORTH ZONE

## **VERTICAL DATUM**

NORTH AMERICAN VERTICAL DATUM-1988

#### SITE BENCHMARK

PROJECT BENCHMARK: (NORTH AMERICAN VERTICAL DATUM-1988)

MONUMENT IN CASE AT N1/4 CORNER SECTION 22, T24N, R6E, WM KING COUNTY SURVEY PT.#2266 PUBLISHED ELEVATION = 397.51 FEET

## **BASIS OF BEARING**

NAD83/91 FROM GPS OBSERVATION MONUMENTED NORTH LINE OF THE NE QUARTER OF SECTION 22, TOWNSHIP 24 NORTH, RANGE 6 E: (BEARING = N 87'39'52" W)

## REFERENCES

CITY OF ISSAQUAH LOT LINE ADJUSTMENT NO. PLŃ04-00065

REC. NO. 20041014900002

PLAT OF ASPEN MEADOWS REC. NO. 20010322001027

RECORD OF SURVEY

REC NO. 198207149002

KING COUNTY SHORT PLAT NO. S89S0278

REC. NO. 199609239015

RECORD OF SURVEY REC NO. 198210209005

SLOPE EASEMENT REC. NO. 20130215000972

QUIT CLAIM DEED REC. NO. 20130215000971

## EQUIPMENT & PROCEDURES

METHOD OF SURVEY: SURVEY PERFORMED BY FIELD TRAVERSE INSTRUMENTATION:

LEICA MS-50 ROBOTIC TOTAL STATION WITH DATA COLLECTOR AND LEICA GS-16 GPS MAINTAINED IN ADJUSTMENT TO MANUFACTURES SPECIFICATIONS AS REQUIRED BY WAC 332-130-100

MEETS OR EXCEEDS STATE STANDARDS WAC 332-130-090

IMPERVIOUS AREAS

**EXISTING IMPERVIOUS:** 0.58 AC (10.9%) **REMOVED IMPERVIOUS:** 0.58 AC (10.9%) REPLACED IMPERVIOUS: NEW IMPERVIOUS:

DISTURBED AREA

**PRELIMINARY DISTURBED AREA:** 231,188 SF (5.30 AC)


# UTILITY NOTE

THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO ANY CONSTRUCTION. AGENCIES INVOLVED SHALL BE NOTIFIED WITHIN A REASONABLE TIME PRIOR TO THE START OF CONSTRUCTION.


6793300250

THE TOPOGRAPHIC SURVEY WAS PERFORMED BY LDC, INC. IN MAY 2021. ANY CHANGES TO THE SITE AFTER THIS DATE WILL NOT BE REFLECTED IN THE PLANS. ANY DISCREPANCIES FOUND BETWEEN WHAT IS SHOWN ON THE PLANS AND WHAT IS NOTED IN THE FIELD SHOULD BE BROUGHT IMMEDIATELY TO THE ATTENTION OF THE ENGINEER.






AND




| JOB NUMBER:   | C21-12      |
|---------------|-------------|
| DRAWING NAME: | C21124P-CS- |
| DESIGNER:     | TF          |
| DRAFTING BY:  | RC          |
| DATE:         | 6-25-       |
| SCALE:        | 1"=6        |
| ILIDIODIOTION | 1004011     |

JRISDICTION: ISSAQUA

SHEET 1 OF 12





ARKLAND HEIGHT

ON WASHING WASHING OF WASHING OF

JOB NUMBER: C21–124

DRAWING NAME: C21124P–T0–PL

DESIGNER: TPA


DRAFTING BY: RCR


DATE: 6–25–21

1"=3
URISDICTION: ISSAQUA

TO-01

I O-01
SHEET 2 OF 12





Surveying<br/>EngineeringNO. DATE<br/>EngineeringNO. DATE<br/>1 10-10-22<br/>PlanningDESCRIPTION<br/>DESCRIPTION<br/>1 10-10-22<br/>DESCRIPTION<br/>DESCRIPTION<br/>TOWMENTSodinville<br/>ind Avenue NE<br/>ille, WA 98072Olympia<br/>Ille, WA 98072

HEIGHTS

PARKLAND HEIGH

SIONAL ENGINEERS

JOB NUMBER: C21-1
DRAWING NAME: C21124P-ERDESIGNER: T
DRAFTING BY: R
DATE: 6-25SCALE: 1"=3

PRAFTING BY:

PATE:

6-25-2

CALE:

1"=30

URISDICTION:

ISSAQUAL

ER-01
SHEET 4 OF 12

2. THE IMPLEMENTATION OF THESE ESC PLANS AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF THESE ESC FACILITIES IS THE RESPONSIBILITY OF THE APPLICANT/ESC SUPERVISOR UNTIL ALL

3. THE BOUNDARIES OF THE CLEARING LIMITS SHOWN ON THIS PLAN SHALL BE CLEARLY FLAGGED BY SURVEY TAPE OR FENCING. IF REQUIRED, PRIOR TO CONSTRUCTION (SWDM APPENDIX D), DURING THE CONSTRUCTION PERIOD, NO DISTURBANCE BEYOND THE CLEARING LIMITS SHALL BE PERMITTED. THE CLEARING LIMITS SHALL BE MAINTAINED BY THE APPLICANT/ESC SUPERVISOR FOR THE DURATION OF CONSTRUCTION.

4. STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES, SUCH AS CONSTRUCTED WHEEL WASH SYSTEMS OR WASH PADS. MAY BE REQUIRED TO ENSURE THAT ALL PAVED AREAS ARE KEPT CLEAN AND TRACK OUT TO ROAD RIGHT OF WAY DOES NOT OCCUR FOR THE DURATION OF THE PROJECT

5. THE ESC FACILITIES SHOWN ON THIS PLAN MUST BE CONSTRUCTED PRIOR TO OR IN CONJUNCTION WITH ALL CLEARING AND GRADING SO AS TO ENSURE THAT THE TRANSPORT OF SEDIMENT TO SURFACE WATERS. DRAINAGE SYSTEMS, FLOW CONTROL BMP LOCATIONS (EXISTING AND PROPOSED), AND ADJACENT PROPERTIES IS MINIMIZED

6. THE ESC FACILITIES SHOWN ON THIS PLAN ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THESE ESC FACILITIES SHALL BE UPGRADED AS NEEDED FOR UNEXPECTED STORM EVENTS AND MODIFIED TO ACCOUNT FOR CHANGING SITE CONDITIONS (E.G. ADDITIONAL COVER MEASURES, ADDITIONAL SUMP PUMPS, RELOCATION OF DITCHES AND SILT FENCES, PERIMETER

PROTECTION ETC.) AS DIRECTED BY THE CITY OF ISSAQUAH 7. THE ESC FACILITIES SHALL BE INSPECTED DAILY BY THE APPLICANT/ESC SUPERVISOR AND MAINTAINED TO ENSURE CONTINUED PROPER FUNCTIONING. WRITTEN RECORDS SHALL BE KEPT OF WEEKLY REVIEWS OF THE

ESC FACILITIES. 8. ANY AREAS OF EXPOSED SOILS, INCLUDING ROADWAY EMBANKMENTS, THAT WILL NOT BE DISTURBED FOR TWO CONSECUTIVE DAYS DURING THE WET SEASON OR SEVEN DAYS DURING THE DRY SEASON SHALL BE IMMEDIATELY STABILIZED WITH THE APPROVED ESC METHODS (E.G., SEEDING, MULCHING, PLASTIC COVERING,

9. ANY AREA NEEDING ESC MEASURES THAT DO NOT REQUIRE IMMEDIATE ATTENTION SHALL BE ADDRESSED WITHIN

10. THE ESC FACILITIES ON INACTIVE SITES SHALL BE INSPECTED AND MAINTAINED A MINIMUM OF ONCE A MONTH DURING THE DRY SEASON, BI-MONTHLY DURING THE WET SEASON, OR WITHIN TWENTY FOUR (24) HOURS FOLLOWING A STORM EVENT.

11. AT NO TIME SHALL MORE THAN ONE (1) FOOT OF SEDIMENT BE ALLOWED TO ACCUMULATE WITHIN A CATCH BASIN. ALL CATCH BASINS AND CONVEYANCE LINES SHALL BE CLEANED PRIOR TO PAVING. THE CLEANING OPERATION SHALL NOT FLUSH SEDIMENT-LADEN WATER INTO THE DOWNSTREAM SYSTEM.

12. ANY PERMANENT RETENTION/DETENTION FACILITY USED AS A TEMPORARY SETTLING BASIN SHALL BE MODIFIED WITH THE NECESSARY EROSION CONTROL MEASURES AND SHALL PROVIDE ADEQUATE STORAGE CAPACITY. IF THE FACILITY IS TO FUNCTION ULTIMATELY AS AN INFILTRATION SYSTEM, THE TEMPORARY FACILITY MUST BE ROUGH GRADED SO THAT THE BOTTOM AND SIDES ARE AT LEAST THREE FEET ABOVE THE FINAL GRADE OF THE PERMANENT FACILITY. FLOW CONTROL BMP AREAS (EXISTING OR PROPOSED) SHALL NOT BE USED AS TEMPORARY FACILITIES AND SHALL BE PROTECTED FROM SEDIMENTATION AND INTRUSION.

13. COVER MEASURES WILL BE APPLIED IN CONFORMANCE WITH APPENDIX D OF THE KING COUNTY SURFACE

WATER DESIGN MANUAL 14. PRIOR TO THE BEGINNING OF THE WET SEASON (OCT. 1), ALL DISTURBED AREAS SHALL BE REVIEWED TO IDENTIFY WHICH ONES CAN BE SEEDED IN PREPARATION FOR THE WINTER RAINS. DISTURBED AREAS SHALL BE SEEDED WITHIN ONE WEEK OF THE BEGINNING OF THE WET SEASON. A SKETCH MAP OF THOSE AREAS TO BE SEEDED AND THOSE AREAS TO REMAIN UNCOVERED SHALL BE SUBMITTED TO THE DPER INSPECTOR.

#### CONSTRUCTION NOTES

BEFORE ANY CLEARING OR GRADING OCCURS, MARK CLEARING LIMITS IN A PROMINENT AND DURABLE MANNER. MAINTAIN UNTIL FINAL APPROVAL

BEFORE ANY CLEARING OR GRADING OCCURS INSTALL PROTECTION FOR TREES AND CRITICAL AREAS/BUFFERS. 3. THE CONTRACTOR SHALL RESTORE TO CURRENT STANDARDS CRITICAL AREAS, AND PUBLIC AND PRIVATE PROPERTY DAMAGED BY CONTRACTOR'S OPERATIONS.

AT ALL TIMES MAINTAIN ACCESS TO BUILDINGS FOR FIRE, PEDESTRIAN AND VEHICULAR ACCESS. 5. INSTALL STEEL PLATES OVER ANY TRENCH, AT ANY TIME WORK IS STOPPED AND THE TRENCH IS OPEN.

# EROSION, SEDIMENTATION AND

<u>WATER QUALITY SITE INSPECTIONS:</u> PRIOR TO ANY SITE DEVELOPMENT WORK TAKING PLACE, A PRE-CONSTRUCTION MEETING WITH THE CONTRACTOR, OWNER, AND CITY INSPECTOR SHALL BE HELD.

THE DEPARTMENT OF ECOLOGY REQUIRES THAT CONSTRUCTION PROJECTS ONE ACRE OR LARGER RETAIN A CESCL TO ENSURE THAT THE PROJECT IS IN COMPLIANCE WITH THE CURRENT EROSION, SEDIMENTATION AND WATER QUALITY STANDARDS. NO CESCL IS REQUIRED FOR THIS PROJECT.

## THE CESCL IS RESPONSIBLE FOR:

INSPECTING THE CONSTRUCTION SITE TO ENSURE THAT ALL CONSTRUCTION SWPPP MEASURES ARE FUNCTIONING AS INTENDED.

ALLOCATING RESOURCES TO REPAIR ALL EROSION CONTROL STRUCTURES THAT ARE IN NEED OF MAINTENANCE. MONITORING WATER QUALITY FOR ANY STORM DRAINAGE THAT LEAVES THE SITE.

D. STOPPING AND/OR REDIRECTING CONSTRUCTION ACTIVITIES DEEMED NECESSARY TO PROTECT THE ENVIRONMENT.

SHOULD BMP PERFORMANCE GOALS NOT BE ACHIEVED, THE ONLY CONSTRUCTION ACTIVITIES THAT SHALL BE ALLOWED ARE THE REPAIR OF EXISTING EROSION CONTROL STRUCTURES, INSTALLATION OF ADDITIONAL BMP'S TO MINIMIZE THE TRANSPORT OF SEDIMENT OFFSITE, OR THOSE ACTIVITIES THAT DO NOT DISTURB EXPOSED EARTH AND DO NOT HAVE THE POTENTIAL TO GENERATE ADDITIONAL SEDIMENT.

# <u>DE-WATERING CONTROL NOTES</u>

ALL TURBID DE-WATERING WATER SHALL BE DISPOSED OF USING ONE OF THE FOLLOWING OPTIONS:

2. TRANSPORT OFFSITE IN A VEHICLE, SUCH AS A VACUUM FLUSH TRUCK, FOR LEGAL DISPOSAL IN A MANNER

THAT DOES NOT POLLUTE STATE WATERS.

ECOLOGY-APPROVED ON-SITE CHEMICAL TREATMENT OR OTHER SUITABLE TREATMENT TECHNOLOGIES, SANITARY SEWER DISCHARGE WITH LOCAL SEWER DISTRICT APPROVAL, IF THERE IS NO OTHER OPTION,

5. USE OF A SEDIMENTATION BAG WITH OUTFALL TO A DITCH OR SWALE FOR SMALL VOLUMES OF LOCALIZED

6. FOUNDATION, VAULT, AND TRENCH DE-WATERING WATER, WHICH HAVE SIMILAR CHARACTERISTICS TO STORMWATER RUNOFF AT THE SITE, SHALL BE DISPERSED TO NATIVE VEGETATION AND/ OR DISCHARGED TO A SEDIMENTATION FACILITY.

# POLLUTANT CONTROL NOTES

ALL POLLUTANTS, INCLUDING WASTE MATERIALS, THAT OCCUR ONSITE SHALL BE HANDLED AND DISPOSED OF IN A MANNER THAT DOES NOT CAUSE CONTAMINATION OF STORMWATER.

2. COVER, CONTAINMENT, AND PROTECTION FROM VANDALISM SHALL BE PROVIDED FOR ALL CHEMICALS, LIQUID PRODUCTS, PETROLEUM PRODUCTS, AND NON-INERT WASTES PRESENT ON THE SITE (SEE CHAPTER 173-304

WAC FOR THE DEFINITION OF INERT WASTE). ONSITE FUELING TANKS SHALL INCLUDE SECONDARY CONTAINMENT. MAINTENANCE AND REPAIR OF HEAVY EQUIPMENT AND VEHICLES INVOLVING OIL CHANGES, HYDRAULIC SYSTEM DRAIN DOWN, SOLVENT AND DE-GREASING CLEANING OPERATIONS, FUEL TANK DRAIN DOWN AND REMOVAL, AND OTHER ACTIVITIES WHICH MAY RESULT IN DISCHARGE OR SPILLAGE OF POLLUTANTS TO THE GROUND OR INTO STORMWATER RUNOFF MUST BE CONDUCTED USING SPILL PREVENTION MEASURES, SUCH AS DRIP PANS. CONTAMINATED SURFACES SHALL BE CLEANED IMMEDIATELY FOLLOWING ANY DISCHARGE OR SPILL INCIDENT EMERGENCY REPAIRS MAY BE PERFORMED ONSITE USING TEMPORARY PLASTIC PLACED BENEATH AND, IF RAINING, OVER THE VEHICLE.

4. APPLICATION OF AGRICULTURAL CHEMICALS, INCLUDING FERTILIZERS AND PESTICIDES, SHALL BE CONDUCTED IN A MANNER AND AT APPLICATION RATES THAT WILL NOT RESULT IN LOSS OF CHEMICAL TO STORMWATER RUNOFF. MANUFACTURERS' RECOMMENDATIONS FOR APPLICATION RATES AND PROCEDURES SHALL BE

MEASURES SHALL BE USED TO PREVENT OR TREAT CONTAMINATION OF STORMWATER RUNOFF BY PH MODIFYING SOURCES. THESE SOURCES INCLUDE, BUT ARE NOT LIMITED TO, BULK CEMENT, CEMENT KILN DUST, FLY ASH, NEW CONCRETE WASHING AND CURING WATERS, WASTE STREAMS GENERATED FROM CONCRETE GRINDING AND SAWING, EXPOSED AGGREGATE PROCESSES, AND CONCRETE PUMPING AND MIXER WASHOUT WATERS. STORMWATER DISCHARGES SHALL NOT CAUSE OR CONTRIBUTE TO A VIOLATION OF THE WATER QUALITY STANDARD FOR PH IN THE RECEIVING WATER.

THE THIRTEEN ELEMENTS OF A CONSTRUCTION SWPPP: . IHE BMPS REFERENCED BELOW ARE PER THE 2014 STORMWATER MANAGEMENT MANUAL FOR WESTERN WASHINGTON:

A PORTION OF THE N 1/2 OF THE NW 1/4 OF SEC 22, TWN 24 N, RGE 6 E, W.M., KING COUNTY, WASHINGTON

MARK CLEARING LIMITS: THE CLEARING LIMITS ARE INDICATED ON THE PLAN SHEET. CLEARING AND GRADING WILL BE LIMITED TO ONLY AREAS THAT NEED TO BE DISTURBED FOR GRADING, AND PLACING OR STOCK PILING FILL AND TO PRESERVE AS MUCH NATURAL VEGETATION AND THE DUFF LAYER AS POSSIBLE. FIELD MARKING THE CLEARING LIMITS SHALL BE COMPLETED PRIOR TO ANY CLEARING OR DISTURBING THE SITE.

> PLASTIC OR METAL FENCE C233 SILT FENCE

ESTABLISH CONSTRUCTION ACCESS: ACCESS TO THE CONSTRUCTION SITE SHALL BE LIMITED TO THE ROCK CONSTRUCTION ENTRANCES.

STABILIZED CONSTRUCTION ENTRANCE C105

CONTROL FLOW RATES: A TEMPORARY SEDIMENT POND AND ASSOCIATED CONTROL STRUCTURE WILL BE USED TO CONTROL FLOW RATES. SEDIMENT-LADEN RUNOFF WILL BE DIRECTED TO POND.

TEMPORARY SEDIMENT POND

INSTALL SEDIMENT CONTROLS: SEDIMENT CONTROL WILL BE PROVIDED THROUGH A COMBINATION OF SILT FENCE, AND THE TEMPORARY DETENTION/ WATER QUALITY POND.

INTERCEPTOR DIKE AND SWALES

C233 SILT FENCE C241 TEMPORARY SEDIMENT POND

STABILIZE SOILS: TEMPORARY AND PERMANENT SOIL STABILIZATION WILL BE PROVIDED. TEMPORARY STABILIZATION WILL BE PROVIDED TO EXPOSED WORKED EARTH. FROM OCTOBER 1 UNTIL APRIL 30, NO EXPOSED SOIL MAY REMAIN EXPOSED AND UNWORKED FOR MORE THAN TWO DAYS: FROM MAY 1 UNTIL SEPTEMBER 30, NO EXPOSED SOIL MAY REMAIN EXPOSED AND UNWORKED FOR MORE THAN SEVEN DAYS.

C120 TEMPORARY AND PERMANENT SEEDING

C121 MULCHING C123 PLASTIC COVERING

PROTECT SLOPES: SLOPES SHALL BE PROTECTED FROM EROSION THROUGH COVER AND SOIL STABILIZATION.

TEMPORARY AND PERMANENT SEEDING C120

C121 MULCHING C123 PLASTIC COVERING

PROTECT DRAIN INLETS: INLET PROTECTION SHALL BE INSTALLED IN ALL CATCH BASINS AND REMAIN UNTIL CONSTRUCTION OF ALL THE RESIDENCES WITHIN THE DEVELOPMENT HAS BEEN COMPLETED. INLET PROTECTION SHALL BE INSPECTED REGULARLY AND THE FILTER FABRIC CLEANED/REPLACED AS NECESSARY. WHEN PROVIDING MAINTENANCE TO THE INLET PROTECTION, THE FABRIC SHALL BE REMOVED IN SUCH A WAY AS TO NOT ALLOW THE RETAINED SEDIMENT TO FALL INTO THE CATCH BASIN.

STORM DRAIN INLET PROTECTION

STABILIZE CHANNELS AND OUTLETS: ALL CHANNEL SLOPES SHALL BE CONSTRUCTED AND PROTECTED AGAINST EROSION.

C207 CHECK DAMS

CONTROL POLLUTANTS: POLLUTANTS SHALL BE CONTROLLED PER POLLUTANT CONTROL NOTES. SEE THIS SHEET FOR NOTES.

10. CONTROL DE-WATERING: DISPOSAL OPTIONS FOR DE-WATERING WATER ARE AS SPECIFIED IN THE DE-WATERING CONTROL NOTES. SEE THIS SHEET FOR NOTES.

11. MAINTAIN BMPS: MAINTENANCE OF THE BMPS IS SPECIFIED IN THE CONSTRUCTION SEQUENCE AND GRADING AND EROSION CONTROL NOTES, SEE SHEET ER-01 AND THIS SHEET.

12. PROJECT MANAGEMENT: THE GRADING AND EROSION CONTROL NOTES SPECIFY SEASONAL WORK LIMITATIONS. BMPS SHALL BE MAINTAINED PER ELEMENT #11.

13. PROTECT LID BMP'S: LOW IMPACT DEVELOPMENT (LID) BMP'S WILL NOT BE USED IN THIS PROJECT.

# SEED OPTIONS MIX

TABLE 4.1 REPRESENTS THE STANDARD MIX FOR THOSE AREAS WHERE JUST A TEMPORARY VEGETATIVE COVER IS REQUIRED.

| TABLE 4.1 TEMPORARY EROSION CONTROL SEED MIX                              |          |          |               |
|---|----------|----------|---------------|
|   | % WEIGHT | % PURITY | % GERMINATION |
| CHEWINGS OR ANNUAL BLUE GRASS<br>FESTUCA RUBRA VAR. COMMUTATA OR POA ANNA | 40       | 98       | 90            |
| PERENNIAL RYE<br>LOLIUM PERENNE   | 40       | 98       | 90            |
| REDTOP OR COLONIAL BENTGRASS<br>AGROSTIS ALBA OR AGROSTIS TENUIS          | 10       | 92       | 85            |
| WHITE DUTCH CLOVER<br>TRIFOLIUM REPENS                                    | 10       | 98       | 90            |


# THIS TURF SEED MIX IN TABLE 4.3 IS FOR DRY SITUATIONS WHERE THERE IS NO NEED FOR MUCH WATER. THE ADVANTAGE IS THAT THIS MIX REQUIRES VERY LITTLE MAINTENANCE.

| TABLE 4.3<br>LOW-GROWING TURF SEED MIX                         |          |          |               |
|--|----------|----------|---------------|
|  | % WEIGHT | % PURITY | % GERMINATION |
| DWARF TALL FESCUE (SEVERAL VARIETIES) FESTUCA ARUNDINACEA VAR. | 45       | 98       | 90            |
| DWARF PERENNIAL RYE (BARCLAY)<br>LOIUM PERENNE VAR. BARELAY    | 30       | 98       | 90            |
| RED FESCUE<br>FESTUCA RUBRA                                    | 20       | 98       | 90            |
| COLONIAL BENTGRASS<br>AGROSTIS TENUIS                          | 5        | 98       | 90            |

TABLE 4.4 PRESENTS A MIX RECOMMENDED FOR BIOSWALES AND OTHER INTERMITTENTLY WET AREAS.

| TABLE 4.4<br>BIOSWALE SEED MIX*                                 |          |          |               |
|---|----------|----------|---------------|
|   | % WEIGHT | % PURITY | % GERMINATION |
| TALL OR MEADOW FESCUE<br>FESTUCA ARUNDINACEA OR FESTICA ELATIOR | 75–80    | 98       | 90            |
| SEASIDE/CREEPING BENTGRASS<br>AGROSTIS PALUSTRIS                | 10-15    | 92       | 85            |
| REDTOP BENTGRASS<br>AGROSTIS ALBA OR AGROSTIS GIGANTEA          | 5–10     | 90       | 80            |

\*MODIFIED BRIARGREEN, INC. HYDROSEEDING GUIDE WETLAND SEED MIX



ROCK CONSTRUCTION ENTRANCE

#### TEMPORARY GRAVEL CONSTRUCTION ENTRANCE:

. INSTALLATION: THE AREA OF THE ENTRANCE SHOULD BE CLEARED OF ALL VEGETATION, ROOTS AND OTHER OBJECTIONABLE MATERIAL. THE GRAVEL SHALI BE PLACED TO THE SPECIFIED DIMENSIONS. ANY DRAINAGE FACILITIES REQUIRED BECAUSE OF WASHING SHOULD BE CONSTRUCTED ACCORDING TO SPECIFICATIONS IN THE PLAN. IF WASH RACKS ARE USED, THEY SHOULD BE INSTALLED ACCORDING TO MANUFACTURER'S SPECIFICATIONS.

2. AGGREGATE: 4" TO 6" CRUSHED BALLAST ROCK.

3. ENTRANCE DIMENSIONS: THE AGGREGATE LAYER MUST BE AT LEAST 6 INCHES THICK. IT MUST EXTEND THE FULL WIDTH OF THE VEHICULAR INGRESS AND EGRESS AREA. THE LENGTH OF THE ENTRANCE MUST BE AT LEAST 100 FEET.

4. WASHING: IF CONDITIONS ON THE SITE ARE SUCH THAT MOST OF THE MUD IS NOT REMOVED FROM VEHICLE TIRES BY CONTACT WITH HE GRAVEL, THEN THE TIRES MUST BE WASHED BEFORE VEHICLES ENTER A PUBLIC ROAD, WASH WATER MUST BE CARRIED AWAY FROM THE ENTRANCE TO A SETTLING AREA TO REMOVE SEDIMENT. A WASH RACK MAY ALSO BE USED TO MAKE WASHING MORE CONVENIENT AND EFFECTIVE.

MAINTENANCE: THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH 2-INCH STONE, AS CONDITIONS DEMAND. AND REPAIR AND/OR CLEAN OUT ANY STRUCTURES USED TO TRAP SEDIMENT. ALL MATERIALS SPILLED. DROPPED. WASHED OR TRACKED FROM VEHICLES ONTO ROADWAY OR INTO STORM DRAINS MUST BE REMOVED

#### MAINTENANCE STANDARDS: 1. QUARRY SPALLS (OR HOG FUEL) SHALL BE ADDED IF THE PAD IS NO


LONGER IN ACCORDANCE WITH THE SPECIFICATIONS.

2. IF THE ENTRANCE IS NOT PREVENTING SEDIMENT FROM BEING TRACKED ONTO PAVEMENT, THEN ALTERNATIVE MEASURES TO KEEP THE STREETS FREE OF SEDIMENT SHALL BE USED. THIS MAY INCLUDE STREET SWEEPING, AN INCREASE IN THE DIMENSIONS OF THE ENTRANCE, OR THE INSTALLATION OF A WHEEL WASH. IF WASHING IS USED, IT SHALL BE DONE ON AN AREA COVERED WITH CRUSHED ROCK, AND WASH WATER SHALL DRAIN TO A SEDIMENT TRAP OR POND. PROVIDE TIRE WASH FOR ALL WINTER GRADING.

3. ANY SEDIMENT THAT IS TRACKED ONTO PAVEMENT SHALL BE REMOVED IMMEDIATELY BY SWEEPING. THE SEDIMENT COLLECTED BY SWEEPING SHALL BE REMOVED OR STABILIZED ON-SITE. THE PAVEMENT SHALL NO BE CLEANED BY WASHING DOWN THE STREET, EXCEPT WHEN SWEEPING IS INEFFECTIVE AND THERE IS A THREAT TO PUBLIC SAFETY. IF IT IS NECESSARY TO WASH THE STREETS, THE CONSTRUCTION OF A SMALL SUMP SHALL BE CONSIDERED. THE SEDIMENT WOULD THEN BE WASHED


4. ANY ROCK SPALLS THAT ARE LOOSENED FROM THE PAD AND END UP ON THE ROADWAY SHALL BE REMOVED IMMEDIATELY.

5. IF VEHICLES ARE ENTERING OR EXITING THE SITE AT POINTS OTHER THAN THE CONSTRUCTION ENTRANCE(S), FENCING (SECTION 5.4.1) SHALL BE INSTALLED TO CONTROL TRAFFIC.









## SEDIMENT POND CROSS SECTION

NOT TO SCALE

UTILITY NOTE

THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO ANY CONSTRUCTION. AGENCIES INVOLVED SHALL BE NOTIFIED WITHIN A REASONABLE TIME PRIOR TO THE START OF CONSTRUCTION.

THE TOPOGRAPHIC SURVEY WAS PERFORMED BY LDC, INC. IN MAY 2021. ANY CHANGES TO THE SITE AFTER THIS DATE WILL NOT BE REFLECTED IN THE PLANS. ANY DISCREPANCIES FOUND BETWEEN WHAT IS SHOWN ON THE PLANS AND WHAT IS NOTED IN THE FIELD SHOULD BE BROUGHT IMMEDIATELY TO THE ATTENTION OF THE ENGINEER.



里


AND N

HORTON

DR

JOB NUMBER: DRAWING NAME: C21124P-ER-DESIGNER: DRAFTING BY: 6-25-1 AS NOTE JRISDICTION: ISSAQUA

SHEET 5 OF 12




HORTON AND


JOB NUMBER:

DRAWING NAME: C21124P-SP-ESIGNER: DRAFTING BY: JURISDICTION:

SHEET **6** OF **12** 



**AND HEIGHT** 




|               | •             |
|---------------|---------------|
| JOB NUMBER:   | C21-124       |
| DRAWING NAME: | C21124P-RD-PR |
| DESIGNER:     | TPA           |
| DRAFTING BY:  | RCR           |
| DATE:         | 6-25-21       |
| SCALE:        | 1"=30         |
|               |               |


JURISDICTION: ISSAQUAF


A PORTION OF THE N 1/2 OF THE NW 1/4 OF SEC 22, TWN 24 N, RGE 6 E, W.M., KING COUNTY, WASHINGTON

**AND HEIGHT** 



| JOB NUMBER:    | C21-124       |
|----------------|---------------|
| DRAWING NAME:  | C21124P-RD-PF |
| DESIGNER:      | TPA           |
| DRAFTING BY:   | RCF           |
| DATE:          | 6-25-2        |
| SCALE:         | 1"=30         |
| ILIDICDICTION. | ICCVULIVI     |






 Engineering lile
 NO. DATE DATE DESCRIPTION
 DATE DESCRIPTION

 Planning
 1 10–10–22 REVISED PER CITY 1ST COMMENTS

 iile venue NE / 498072
 Olympia


 pp.com
 F 425.482.2893

ARKLAND HEIGHT





| JOB NUMBER:   | C21-124       |
|---------------|---------------|
| DRAWING NAME: | C21124P-RD-PI |
| DESIGNER:     | TPA           |
| DRAFTING BY:  | RCF           |
| DATE:         | 6-25-2        |
| SCALE:        | 1"=30         |
| HIDICDIOTION  | ICCAOLIAI     |


RD-04















UTILITY NOTE

THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO ANY CONSTRUCTION.
AGENCIES INVOLVED SHALL BE NOTIFIED WITHIN A REASONABLE TIME PRIOR TO THE START OF CONSTRUCTION.

## **DISCLAIMER**

THE TOPOGRAPHIC SURVEY WAS PERFORMED BY LDC, INC. IN MAY 2021. ANY CHANGES TO THE SITE AFTER THIS DATE WILL NOT BE REFLECTED IN THE PLANS. ANY DISCREPANCIES FOUND BETWEEN WHAT IS SHOWN ON THE PLANS AND WHAT IS NOTED IN THE FIELD SHOULD BE BROUGHT IMMEDIATELY TO THE ATTENTION OF THE ENGINEER.





AND HEIGHT DR HORTON

DRAWING NAME: C21124P-RD-DESIGNER: DRAFTING BY: JURISDICTION:

- CONTRACTORS SHALL LIMIT ALL CONSTRUCTION ACTIVITIES AND HEAVY EQUIPMENT OPERATION TO BETWEEN 7:00 AM AND 6:00 PM MONDAY THROUGH
- FRIDAY, EXCLUDING HOLIDAYS PER IMC 16.35.010; EXTENDED WORK HOURS MUST BE APPROVED IN WRITING BY DSD. 1.2 ALL CONTRACTORS AND SUBCONTRACTORS PROVIDING SERVICE WITHIN THE CITY LIMITS OF ISSAQUAH SHALL OBTAIN A CITY OF ISSAQUAH BUSINESS
- 1.3 CONTRACTORS SHALL HAVE COPIES OF THE APPROVED PLANS, APPLICABLE CITY STANDARDS, AND THE SPILL RESPONSE PLAN ON—SITE AT ALL TIMES. THE "CITY STANDARDS" REFER TO THE CITY OF ISSAQUAH STREET STANDARDS DATED 2010, CITY OF ISSAQUAH WATER STANDARDS DATED OCTOBER 2013, AND CITY OF ISSAQUAH SEWER STANDARDS DATED 1988 AND REVISED 2005. GENERAL STANDARD DETAILS AND APPROVED MATERIALS LIST CAN CURRENTLY BE FOUND IN THE WATER STANDARDS AND APPLY TO ALL PROJECT ELEMENTS. SOME OF THESE CITY STANDARDS HAVE NOT BEEN STAMPED BY A PROFESSIONAL ENGINEER AND, PER WAC 196-23-020, THEY ARE PROVIDED AS ENGINEERING DESIGN AIDS ONLY. CONTRACTORS SHALL CONTACT THE ENGINEER AND DSD PRIOR TO USING ANY ELEMENTS OF THE CITY STANDARDS THAT ARE NOT SPECIFICALLY CALLED OUT IN THE GENERAL NOTES FOR ISSAQUAH ROADS & UTILITIES OR SHOWN ON THE PLANS & SPECIFICATIONS. CITY STANDARDS SHALL NOT BE APPROVED FOR USE UNLESS THEY ARE SPECIFICALLY REFERENCED IN THE APPROVED CONSTRUCTION PLANS OR THROUGH A DESIGN CHANGE APPROVED BY DSD. 1.4 CONTRACTORS SHALL REFUEL ALL EQUIPMENT ON—SITE USING DSD APPROVED METHODS AND PROCEDURES.
- 1.5 CONTRACTORS SHALL PROVIDE DSD INSPECTOR WITH A MATERIALS LIST A MINIMUM OF TEN WORKING DAYS BEFORE INSTALLATION. THE LIST SHALL INCLUDE MANUFACTURER AND/OR MODEL NUMBER (IF APPLICABLE) OF MATERIAL AND EQUIPMENT TO BE INSTALLED. THE MANUFACTURER'S TECHNICAL SPECIFICATIONS FOR PIPE, APPURTENANCES AND EQUIPMENT SHALL BE SUPPLIED TO DSD UPON REQUEST
- 1.6 CONTRACTORS SHALL LAY ALL WATER, SEWER AND STORM DRAINAGE PIPELINES "UP-HILL" STARTING AT THE LOWEST MAIN ELEVATION. THE MAIN SHALL BE POSITIONED SO THAT THE BELL END IS ON THE HIGHER SIDE OF THE PIPE SEGMENT AND THE PLAIN END INSERTED INTO THE BELL END. PIPE ENDS SHALL NOT BE DRIVEN HOME, BUT SHALL BE POSITIONED WITH ADEQUATE ROOM FOR THERMAL EXPANSION OF THE PIPE NETWORK
- WITHOUT BUCKLING OR COMPRESSION OF THE JOINTS. 1.7 CONTRACTORS SHALL PLACE TRENCH BACKFILL IN UNIFORM LOOSE LIFTS NOT EXCEEDING 12-INCHES IN THICKNESS IN NON-TRAVELED AREAS OR 6-INCHES IN TRAVELED AREAS. TRENCH BACKFILL LOCATED BETWEEN THE BOTTOM OF THE PIPE AND 6-INCHES ABOVE THE PIPE CROWN SHALL NOT CONTAIN ROCKS LARGER THAN 3-INCHES IN DIAMETER. TRENCH BACKFILL LOCATED ABOVE THE PIPE ZONE SHALL MEET WSDOT SPEC. 9-03.14(3) OR AS APPROVED BY DSD. TRENCH BACKFILL LOCATED WITHIN THE TOP 4-FEET SHALL BE COMPACTED TO A MINIMUM OF 95 PERCENT OF THE SOIL'S MAXIMUM DRY DENSITY AS DETERMINED USING MODIFIED PROCTOR. COMPACTION TESTING IN TRENCHES GREATER THAN 4 FT. IN DEPTH MAY BE ACCOMPLISHED BY MAINTAINING A COMPACTION PATTERN PROVEN TO MEET COMPACTION REQUIREMENTS. ALL NON WSDOT SPEC. MATERIAL SHALL INCLUDE GRADATION REPORT FOR DSD REVIEW AND APPROVAL PRIOR TO PLACEMENT.
- 1.8 CONTRACTORS SHALL NOT INSTALL ABOVE GROUND COPPER OR GALVANIZED MATERIALS OTHER THAN VAULT LIDS OR OTHER DSD APPROVED ITEMS. 1.9 DEVELOPER SHALL CONTRACT WITH A GEO-TECHNICAL ENGINEER LICENSED IN THE STATE OF WASHINGTON TO SUPERVISE ALL TRENCH AND ROADWAY BACKFILL AND SIGNIFICANT GRADING ACTIVITIES. CONSTRUCTION RECORDS OF SOIL PLACEMENT AND COMPACTION TESTING SHALL BE TRANSMITTED TO DSD ON A WEEKLY BASIS. ALL TESTS SHALL INCLUDE A MAP SHOWING THE TESTING LOCATION, THE ISSAQUAH SW (FORMERLY PUB) # AND NAME OF PLAN SET USED FOR CONSTRUCTION. A SEPARATE REPORT SHALL BE ISSUED FOR EACH SW #
- 1.10 DEVELOPER SHALL SCHEDULE A PRE-CONSTRUCTION MEETING WITH DSD PRIOR TO ANY CONSTRUCTION ACTIVITY. 1.11 THE FOLLOWING ORDER OF PRECEDENCE SHALL APPLY IF THERE ARE INCONSISTENCIES BETWEEN THE DIFFERENT ELEMENTS OF THE CONSTRUCTION PLANS: 1) DSD APPROVED FIELD CHANGES, 2) DSD APPROVED DESIGN CHANGES, 3) DSD APPROVED PLANS & SPECIFICATIONS, 4) GENERAL NOTES FOR ISSAQUAH ROADS & UTILITIES, AND 5) WSDOT STANDARD SPECIFICATIONS FOR ROAD, BRIDGE AND MUNICIPAL CONSTRUCTION, CURRENT EDITION.
- 1.12 A COPY OF THE APPROVED PERMIT AND PLANS SHALL BE ON SITE AT ALL TIMES DURING CONSTRUCTION ACTIVITIES.

#### 2. WATER

- CONTRACTORS SHALL USE CLASS 52 OR THICKER DUCTILE IRON MEETING AWWA C151. PIPE AND FITTINGS SHALL HAVE CEMENT-MORTAR LINING MEETING AWWA C104. FITTINGS SHALL BE CAST IRON OR DUCTILE IRON MEETING THE REQUIREMENTS OF AWWA C110 OR AWWA C153. 2.2 CONTRACTORS SHALL INSTALL WATER MAINS WITH A MINIMUM DEPTH OF COVER OF 36"AND A MAXIMUM DEPTH OF COVER OF 60"UNLESS SHOWN
- OTHERWISE ON THE APPROVED CONSTRUCTION DRAWINGS. CONTRACTORS SHALL INSTALL ALL WATER MAINS SO THAT THEY ARE RESTRAINED FROM UNRESOLVED HYDROSTATIC THRUST FORCES IN ACCORDANCE WITH THE APPROVED DESIGN PLANS CHANGES TO THE APPROVED THRUST RESTRAINT SYSTEM SHALL NOT BE MADE WITHOUT DSD APPROVAL. DSD
- INSPECTION OF BLOCKING AND RESTRAINED PIPE SYSTEMS IS REQUIRED PRIOR TO BACKFILL 2.4 USE ROMAC STYLE GRIP RINGS OR DOMESTIC ALTERNATIVE, FOREIGN-MANUFACTURED RESTRAINED-JOINT SYSTEM COMPONENTS SHALL NOT BE USED. CONTRACTORS SHALL TEST ALL WATER MAINS, WATER MAIN APPURTENANCES, AND SERVICE CONNECTIONS EXCLUDING THE METER SETTER ASSEMBLY TO 150 PSI OVER THE NORMAL WORKING PRESSURE. METER SETTER ASSEMBLIES SHALL BE VISUALLY INSPECTED FOR LEAKS AT MAXIMUM NORMAL WORKING PRESSURE. TEST PROCEDURES SHALL CONFORM TO APWA STANDARDS. PIPE PRESSURE RATING SHALL BE AT LEAST 150 PSI IN EXCESS OF
- THE WORKING. 2.6 HYDRANT LATERALS LESS THAN 50'LONG SHALL BE 6", LONGER THAN 50'SHALL BE 8". ALL HYDRANT RUNS SHALL BE SHACKLED AND BLOCKED. HYDRANTS SHALL BE SUPPLIED WITH 5"STORZ TYPE ADAPTERS.
- 2.7 CONTRACTORS SHALL INSTALL AIR AND VACUUM RELEASE VALVES PER THE WATER STANDARDS. VALVE SIZE SHALL BE INDICATED ON THE PLANS. THE ABOVE GRADE PORTIONS OF THE PIPE SHALL BE COATED WITH TWO COATS OF ALKYD BASED HIGH-GLOSS WHITE PAINT.
- 2.8 CONTRACTORS SHALL INSTALL 2-PIECE VALVE BOXES. 2.9 CONTRACTORS SHALL INSTALL SADDLE SERVICE CONNECTIONS WITH DOUBLE STRAPS USED ON 12" OR LARGER SIZES. CONNECTIONS TO BE MADE ON
- PRESSURIZED WATER MAIN ONLY.
- 2.10 CONTRACTORS SHALL INSTALL 1/2" AND 1" SERVICE LINES WITH A MINIMUM DEPTH OF 24" AND A SERVICE LINE TAP OF 30" FROM THE SPRING LINE OF
- 2.11 CONTRACTORS SHALL INSTALL 11/2" AND 2" SERVICE LINES WITH A MINIMUM DEPTH OF 24" AND A SERVICE LINE TAP OF 10' FROM THE SPRING LINE 2.12 CONTRACTORS SHALL INSTALL X AND 1" SERVICES IN ACCORDANCE WITH THE WATER STANDARDS. A PVC PIPE SPACER SHALL BE INSTALLED BETWEEN
- THE SETTER. THE SPACER SHALL BE CUT TO THE APPROPRIATE LENGTH AND IT SHALL CONTAIN A 3/8" DRILLED HOLE (VISIBLE FROM ABOVE). METERS CLOSER THAN 6 FEET SHALL HAVE A 2" PVC CONDUIT BETWEEN THE METER BOXES. 2.13 CONTRACTORS SHALL INSTALL 112" AND 2" SERVICES IN ACCORDANCE WITH THE WATER STANDARDS. A PVC PIPE SPACER SHALL BE INSTALLED BETWEEN
- THE SETTER. THE SPACER SHALL BE CUT TO THE APPROPRIATE LENGTH AND IT SHALL CONTAIN A 3/8" DRILLED HOLE (VISIBLE FROM ABOVE). 2.14 CONTRACTORS SHALL INSTALL WATER METER SETTERS TO A HORIZONTAL AND VERTICAL PLACEMENT TOLERANCE OF PLUS OR MINUS 1-INCH. WATER METER BOXES SHALL BE CENTERED IN THE PLANTER STRIP TO A TOLERANCE OF PLUS OR MINUS 2-INCHES.
- 2.15 ALL NEWLY INSTALLED METERS SHALL BE PROTECTED FROM CONTINUING CONSTRUCTION ACTIVITIES WITH ORANGE, PLASTIC TEMPORARY FENCING. 2.16 CONTRACTORS SHALL INSTALL DOH APPROVED BACKFLOW PREVENTION DEVICES ON ALL IRRIGATION SERVICES. CONTRACTOR SHALL PROVIDE
- INDEPENDENT CERTIFICATION TO DSD INSPECTOR PRIOR TO INSTALLATION. 2.17 CONTRACTORS SHALL INSTALL ONE PIECE OF TYPE K COPPER FROM WATER MAIN TO METER SETTER FOR ALL SERVICE LINES. THE SERVICE LINE
- SHALL BE LOCATED PERPENDICULAR TO THE WATER MAIN. 2.18 CONTRACTORS SHALL INSTALL RESILIENT SEAT TYPE (AWWA C-509) AVK SERIES 65 GATE VALVES PER CITY STANDARDS.
- 2.19 CONTRACTORS SHALL NOT CONNECT NEW MAINS TO THE CITY'S POTABLE WATER SYSTEM UNTIL THE MAINS HAVE PASSED PRESSURE AND PURITY TESTING AND HAVE BEEN APPROVED FOR CONNECTION BY DSD. CONTRACTORS SHALL PERFORM A HIGH FLOW FLUSH AS DIRECTED BY DSD IMMEDIATELY AFTER THE MAIN IS CONNECTED TO THE CITY WATER SUPPLY.
- 2.20 ALL FLOW INTERRUPTIONS SHALL BE SCHEDULED WITH CITY'S PUBLIC WORKS OPERATIONS AT LEAST 14 CALENDAR DAYS AHEAD. ALL FLOW INTERRUPTIONS, INDIVIDUALLY, SHALL BE NO LONGER THAN 8-CONSECUTIVE HOURS LEAVING 16-CONSECUTIVE HOURS FOR STORAGE RECOVERY. THESE INSTRUCTIONS ARE IN ADDITION TO, OR MODIFICATION TO, EXISTING CITY STANDARD OPERATING PROCEDURES FOR SCHEDULED WATER MAIN SHUT-DOWNS.

## 3. SEWER

- 3.1. CONTRACTORS SHALL CONSTRUCT ALL SEWER PIPELINES WITH MINIMUM CLASS 50 DUCTILE IRON OR SOLID WALL PVC PIPE CONFORMING TO REQUIREMENTS OF ASTM D3034 SDR 35 WITH ELASTOMERIC JOINT GASKETS CONFORMING TO ASTM F 477. SEWER PIPE MATERIAL SHALL BE DETERMINED BY THE ENGINEER AND SHOWN ON THE PLANS.
- 3.2. CONTRACTORS SHALL CONSTRUCT ALL PRESSURE SEWER PIPELINES WITH CLASS 52 DUCTILE IRON OR HDPE PIPE. HDPE PIPE SHALL INCLUDE LOCATE WIRE PER CITY STANDARDS.
- 3.3. CONTRACTORS SHALL INSTALL FRAMES AND COVERS MODIFIED TO HAVE 3" RAISED LETTERS MARKED "SEWER" WITH INTEGRAL CAST LIFT HANDLE. MANHOLES LOCATED IN PAVED ROW AREAS SHALL HAVE STANDARD, NON-LOCKING COVERS AND ACCESS LOCATED OUTSIDE OF STORM WATER FLOW LINES. MANHOLES IN UNPAVED AREAS AND IN EASEMENTS TO HAVE LOCKING COVERS.
- 3.4. CONTRACTORS SHALL AIR AND DEFLECTION TEST ALL GRAVITY SEWER PIPE. HDPE PRESSURE SEWER PIPELINES SHALL BE PRESSURE TESTED TO 150-PERCENT OF THE DESIGN OPERATING PRESSURE FOR 30-MINUTES. DUCTILE IRON PRESSURE SEWER PIPELINES SHALL BE PRESSURE TESTED TO THE GREATER OF 150 PSI OVER THE DESIGN WORKING PRESSURE OR NO LESS THAN 200 PSI.
- 3.5. CONTRACTORS SHALL MARK ALL SEWER STUBS WITH A 2X4 POST STENCILED "SEWER" IN 2- INCH LETTERS WITH THE ELEVATION OF THE STUB INVERT PERMANENTLY MARKED. MARKER TO BE ATTACHED TO PIPE INVERT WITH MINIMUM 12 GAUGE WIRE. CONTRACTOR SHALL EXPOSE, SURVEY, AND BACKFILL ALL SEWER STUBS INSTALLED WITHOUT 2X4 POSTS AND INVERT ELEVATIONS. PROVIDING THE DEPTH TO THE SEWER STUB IS NOT ACCEPTABLE. CONTRACTOR MUST PROVIDE ACTUAL INVERT ELEVATION.
- 3.6. CONTRACTORS SHALL VIDEO INSPECT ALL GRAVITY SEWER PIPE AFTER THE ENTIRE SEWER SYSTEM IS INSTALLED AND CLEANED (INCLUDING MANHOLE CHANNELING AND DEBRIS REMOVAL). IMMEDIATELY PRIOR TO VIDEO INSPECTION, CONTRACTOR SHALL POUR 10 GALLONS OF CLEAN WATER INTO THE UPSTREAM MANHOLE. VIDEO INSPECTION TO BE SUCH THAT ENTIRE SEGMENT OF PIPE BETWEEN ADJACENT MANHOLES IS VIDEO TESTED WITHOUT INTERRUPTION. A COPY OF THE VIDEO (DVD FORMAT) INSPECTION SHALL BE SEALED IN A TAMPER PROOF ENVELOPE AND PROVIDED TO DSD PRIOR
- TO ACCEPTANCE OF THE SEWER SYSTEM. 3.7. CONTRACTORS SHALL INSTALL ALL MANHOLE DROPS ON THE EXTERIOR OF THE MANHOLE UNLESS OTHERWISE APPROVED. ALL DROPS SHALL BE
- EQUIPPED WITH A "HALF-PLUG". INSPECTION OF BLOCKING REQUIRED PRIOR TO BACKFILL ON ALL OUTSIDE DROPS. 3.8. CONTRACTORS SHALL PLUG THE CONNECTION TO THE DOWNSTREAM SYSTEM PRIOR TO BEGINNING CONSTRUCTION. PLUG SHALL NOT BE REMOVED
- UNTIL CLEANING OF THE PROPOSED SEWER SYSTEM IS COMPLETE. 3.9. PIPE BEDDING SHALL CONFORM TO WSDOT 9-03.12(3) GRAVEL BACKFILL FOR PIPE ZONE BEDDING.

# 4. STORM WATER

- 4.1. CONTRACTORS SHALL CONSTRUCT STORM PIPELINES AS IDENTIFIED ON THE APPROVED MATERIALS LIST. PIPE SHALL BE RATED FOR H20 SURFACE LOADS WHEN INSTALLED IN AREAS SUBJECT TO TRAFFIC.
- 4.2. CONTRACTORS SHALL INSTALL VANE TYPE CATCH BASIN GRATES UNLESS OTHERWISE NOTED.
- 4.3. CONTRACTORS SHALL INSTALL A 2X4 POST STENCILED "STORM" IN 2-INCH LETTERS WITH THE ELEVATION OF THE STUB INVERT PERMANENTLY MARKED. MARKER TO BE ATTACHED TO PIPE INVERT WITH MINIMUM 12 GAUGE WIRE. CONTRACTOR SHALL EXPOSE, SURVEY, AND BACKFILL ALL STUBS INSTALLED WITHOUT 2X4 POSTS AND INVERT ELEVATIONS. PROVIDING THE DEPTH TO THE STUB IS NOT ACCEPTABLE. CONTRACTOR MUST PROVIDE ACTUAL INVERT ELEVATION.

#### 5. STREETS & SIDEWALKS

- 5.1. CONTRACTORS SHALL INSTALL PERMANENT ROADWAY MONUMENTS AT ALL PC'S, PT'S AND AT INTERSECTIONS. THE MONUMENTS SHALL BE IN ACCORDANCE WITH CITY STANDARD DETAILS.
- 5.2. CONTRACTORS SHALL COMPACT ROADWAY SUBGRADE IN UNIFORM LOOSE LIFTS NOT EXCEEDING 12 INCHES AND COMPACTED TO A MINIMUM OF 95 PERCENT OF THE SOIL'S MAXIMUM DRY DENSITY AS DETERMINED USING MODIFIED PROCTOR. RECYCLED ASPHALT PAVEMENT AND MINERAL AGGREGATE MAY BE USED FOR ROAD SUBGRADE IF APPROVED BY THE GEOTECHNICAL ENGINEER PRIOR TO PLACEMENT. ALL SUBGRADE SHALL BE INSPECTED BY DSD PRIOR TO PLACEMENT OF BASE COURSE AND OTHER ROADWAY MATERIALS. HOT MIX ASPHALT SHALL BE COMPACTED TO 92% OF THE MAXIMUM
- 5.3. CONTRACTORS SHALL REQUEST A PRE-FINAL LIFT (WEARING COURSE) INSPECTION FROM THE DSD A MINIMUM OF ONE BUSINESS DAY PRIOR TO FINAL LIFT PLACEMENT. THE DSD WILL INSPECT AND APPROVE THE ATB SURFACE PRIOR TO INSTALLATION OF THE FINAL LIFT. FINAL LIFT PAVING
- THAT IS PLACED WITHOUT DSD INSPECTION IS SUBJECT TO REMOVAL AND REPAIR AT THE CONTRACTOR'S SOLE COST. 5.4. DEVELOPER SHALL CONTRACT WITH A GEO-TECHNICAL ENGINEER LICENSED IN THE STATE OF WASHINGTON TO TEST THE SUBGRADE AT 200' MINIMUM
- SPACING FOR COMPLIANCE WITH THE COMPACTION STANDARD. 5.5 CONTRACTORS SHALL INSTALL CONCRETE SIDEWALKS WITH A BROOM FINISH AND 4-INCH SHINERS AT ALL EXPANSION JOINTS AND ALL EXPOSED EDGES, UNLESS OTHERWISE NOTED. SIDEWALKS SHALL BE 6-INCH MINIMUM THICKNESS WHERE SUBJECT TO TRAFFIC LOADS AND 4-INCH MINIMUM THICKNESS ELSEWHERE. EXPANSION JOINTS SHALL BE PLACED NO MORE THAN 20-FEET APART. CONCRETE SHALL BE PLACED OVER 4-INCHS OF COMPACTED SUBGRADE CONFORMING TO WSDOT 9-03.9(3).
- 5.6. CONTRACTORS SHALL REQUEST A PRE-POUR INSPECTION IN WRITING FROM DSD A MINIMUM OF ONE BUSINESS DAY PRIOR TO POURING ANY WHEELCHAIR RAMPS. DSD WILL INSPECT AND APPROVE THE WHEELCHAIR RAMP FORMS FOR ALIGNMENT BY SIGNING THE CONTRACTOR'S RED-LINE PLANS. WHEELCHAIR RAMPS THAT ARE POURED WITHOUT DSD INSPECTOR WRITTEN APPROVAL ARE SUBJECT TO REMOVAL AND REPLACEMENT AT THE CONTRACTOR'S SOLE COST. INSPECTION FOR ADA COMPLIANCE WILL BE CONDUCTED FOLLOWING THE CONCRETE POUR AND CURE.
- 5.7. SIDEWALKS, RAMPS, AND DRIVEWAYS THAT PROVIDE PEDESTRIAN ACCESSIBLE ROUTES SHALL COMPLY WITH THE FOLLOWING: CHANGES IN LEVEL UP TO 1/4-INCH MAY BE VERTICAL AND WITHOUT EDGE TREATMENT. CHANGES IN LEVEL BETWEEN 1/4-INCH AND 1/4-INCH SHALL BE BEVELED WITH A SLOPE NO GREATER THAN 1V:2H, CHANGES IN LEVEL GREATER THAN 1/2-INCH SHALL NOT BE ALLOWED.

#### 6. CLEARING, GRADING AND EARTHWORKS

- 6.1. CONTRACTORS MAY WORK USING THE APPROVED TESC MEASURES SHOWN ON THE PLANS. CONTRACTORS SHALL KEEP ALL ROADWAYS CLEAN AND FREE OF SEDIMENT, MUD. ROCK AND DEBRIS.
- 6.2. CONTRACTORS SHALL COMPACT ALL BUILDING AND PAVEMENT AREAS LOCATED OUTSIDE OF PUBLIC RIGHTS-OF-WAYS IN UNIFORM LOOSE LIFTS NOT EXCEEDING 12 INCHES AND SHALL BE COMPACTED TO A MINIMUM OF 95 PERCENT OF THE SOIL'S MAXIMUM DRY DENSITY AS DETERMINED USING MODIFIED PROCTOR.
- 1. TESC COORDINATION a. THE APPLICANT MUST DESIGNATE A TESC SUPERVISOR WHO SHALL BE RESPONSIBLE FOR THE PERFORMANCE, MAINTENANCE, AND REVIEW OF TESC MEASURES AND FOR COMPLIANCE WITH ALL PERMIT CONDITIONS RELATING TO TESC. THE TESC SUPERVISOR SHALL BE A CERTIFIED EROSION AND SEDIMENT CONTROL LEAD AS DEFINED BY THE DEPARTMENT OF ECOLOGY. NOTE: THE APPLICANT IS ULTIMATELY RESPONSIBLE FOR PERMIT COMPLIANCE, REGARDLESS OF WHO HIRES THE TESC SUPERVISOR.
- b. AN ONSITE TESC PRECONSTRUCTION MEETING SHALL BE HELD BEFORE ANY WORK BEGINS TO REVIEW IMPLEMENTATION OF THE TESC PLANS. c. ANY PERMANENT FLOW CONTROL OR WATER QUALITY FACILITY USED AS A TEMPORARY SETTLING BASIN SHALL BE MODIFIED WITH THE NECESSARY EROSION CONTROL MEASURES AND SHALL PROVIDE ADEQUATE STORAGE CAPACITY. INFILTRATION FACILITIES SHALL NOT BE USED FOR TESC.
- 2. TESC INSTALLATION
- a. TESC FACILITIES ARE REQUIRED YEAR ROUND. b. A TESC FIELD PRECON IS REQUIRED WITH THE DSD INSPECTOR PRIOR TO CONSTRUCTION.
- c. THE TESC FACILITIES REQUIRED BY THE PERMIT MUST BE CONSTRUCTED PRIOR TO OR IN CONJUNCTION WITH ALL CLEARING AND GRADING SO AS TO ENSURE THAT THE SEDIMENT-LADEN WATER DOES NOT ENTER THE CITY DRAINAGE SYSTEM, SURFACE WATERS, OR WETLANDS. ADJACENT PROPERTIES SHALL BE PROTECTED FROM SEDIMENT-LADEN RUNOFF.
- d. THE BOUNDARIES OF ANY CLEARING LIMITS AND TREE PROTECTION INCLUDED IN THE PLAN SHALL BE CLEARLY FLAGGED BY SURVEY TAPE OR FENCING PRIOR TO CONSTRUCTION. NO DISTURBANCE BEYOND THE CLEARING LIMITS IS ALLOWED. THE CLEARING LIMITS SHALL BE MAINTAINED BY THE TESC SUPERVISOR FOR THE DURATION OF CONSTRUCTION, UNTIL FINAL LANDSCAPING OR OTHER PERMANENT SITE STABILIZATION.
- e. ANY STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ONSITE ROADS AND PAVED AREAS SHALL BE KEPT CLEAN TO MINIMIZE TURBIDITY IN RUNOFF. ADDITIONAL MEASURES, SUCH AS CONSTRUCTED WHEEL WASH SYSTEMS OR WASH PADS, SHALL BE REQUIRED IF NEEDED TO ENSURE SEDIMENT IS NOT TRACKED OUT TO CITY STREETS. ANY DIRT TRACKED ONTO CITY STREETS SHALL BE SWEPT AS NEEDED OR AS DIRECTED BY THE CITY OF ISSAQUAH. STREET SWEEPING IS NOT CONSIDERED A TESC MEASURE.
- f. TESC MEASURES SHALL BE APPLIED IN ACCORDANCE WITH THE 2012/2014 ECOLOGY STORM WATER MANAGEMENT MANUAL FOR WESTERN WA, VOLUME II CONSTRUCTION STORM WATER POLLUTION PREVENTION.
- q. ANY AREAS OF EXPOSED SOILS, INCLUDING ROADWAY EMBANKMENTS, THAT WILL NOT BE DISTURBED FOR TWO CONSECUTIVE DAYS DURING THE WET SEASON (OCT 1 TO APRIL 30) OR SEVEN DAYS DURING THE DRY SEASON (MAY 1 TO SEPT 30) SHALL BE IMMEDIATELY STABILIZED WITH APPROVED TESC METHODS (E.G. SEEDING, MULCHING, PLASTIC COVERING, ETC.). THESE TIME LIMITS MAY BE MODIFIED BY THE CITY TO ADDRESS SPECIFIC SITE CONDITIONS.
- h. PRIOR TO THE BEGINNING OF THE WET SEASON (OCT 1), ALL DISTURBED AREAS SHALL BE REVIEWED TO IDENTIFY WHICH ONES CAN BE SEEDED OR OTHERWISE COVERED IN PREPARATION FOR THE WINTER RAINS. IF COVER MEASURES ARE NOT ESTABLISHED BY OCT 1, ADDITIONAL TESC MEASURES SHALL BE REQUIRED. TURBIDITY MONITORING:
- a. DISCHARGE FROM THE PROJECT SITE SHALL NOT EXCEED THE NTU LIMIT AT ALL TIMES UP TO THE 10 YEAR/24 HOUR STORM EVENT. THIS EVENT IS DEFINED AS 3.5 INCHES OF RAINFALL OVER A 24 HOUR PERIOD, AS MEASURED AT THE CITY'S RAIN GAGE. THE DISCHARGE LIMIT TO A NATURAL WATER BODY IS 5 NTU OVER BACKGROUND, OTHERWISE THE LIMIT SHALL BE 100 NTU. EXCEEDANCE OF THE NTU LIMIT IS CONSIDERED A VIOLATION OF THE PERMIT AND IS SUBJECT TO STOP WORK AND CODE VIOLATION PENALTIES.
- b. THE CITY OF ISSAQUAH WILL MEASURE THE TURBIDITY OF THE DISCHARGE AT THE DESIGNATED MONITORING POINTS TO VERIFY COMPLIANCE WITH THE DISCHARGE LIMIT. THE TESC SUPERVISOR SHALL BE NOTIFIED OF DISCHARGES ABOVE BACKGROUND OR 25 NTUS AS APPLICABLE, SO THAT ACTION CAN BE TAKEN TO KEEP DISCHARGES BELOW THESE THRESHOLD LEVELS. FOR PROJECT SITES WHERE DESIGNATING A MONITORING POINT IS NOT FEASIBLE (E.G. FLAT SITES), THE MONITORING LOCATIONS WILL BE AT THE DISCRETION OF THE CITY OF ISSAQUAH.
- c. MONITORING POINTS SHALL BE READILY ACCESSIBLE TO THE CITY OF ISSAQUAH AT ALL TIMES FOR ALL PHASES OF CONSTRUCTION. d. ANY DISCHARGE AT 100 NTU OR HIGHER REQUIRES NOTIFICATION TO CITY INSPECTOR, AND MAY BE SUBJECT TO FINES AND PENALTIES.
- e. ANY DISCHARGE TO A STREAM, LAKE OR WETLAND SHALL NOT EXCEED WATER QUALITY STANDARDS PER WAC 173-201A. FAILURE TO MEET WAC 173-201A IS CONSIDERED A VIOLATION OF THE PERMIT AND IS SUBJECT TO STOP WORK AND CODE VIOLATION PENALTIES. 4. ROUTINE TESC MAINTENANCE
- a. THE TESC FACILITIES SHALL BE INSPECTED BY THE TESC SUPERVISOR DAILY OR MORE OFTEN DURING RAINFALL, AND MAINTAINED TO ENSURE PROPER FUNCTIONING. WRITTEN DOCUMENTATION IS REQUIRED FOR DISCHARGES ABOVE THE THRESHOLD LEVELS AND SHALL BE READILY AVAILABLE AT THE PROJECT SITE.
- b. THE TESC FACILITIES SHOWN ON THIS PLAN ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD. THESE TESC FACILITIES SHALL BE MODIFIED AS NEEDED FOR UNEXPECTED STORM EVENTS OR OTHER UNFORESEEN CIRCUMSTANCES, AND TO ACCOUNT FOR CHANGING SITE CONDITIONS (E.G. ADDITIONAL COVER MEASURES, ADDITIONAL SUMP PUMPS, RELOCATION OF DITCHES AND SILT FENCES, PERIMETER PROTECTION ETC.).
- c. THE TESC SUPERVISOR SHALL NOTIFY THE CITY OF ISSAQUAH PRIOR TO PUMPING ANY DISCHARGE OFFSITE OR TO CRITICAL AREAS. d. TESC FACILITIES ON INACTIVE SITES SHALL BE INSPECTED AND MAINTAINED A MINIMUM OF ONCE A MONTH OR WITHIN 24 HOURS FOLLOWING A STORM EVENT.
- 5. UPDATED TESC PLANS a. REVISED TESC PLANS SHALL BE SUBMITTED TO THE CITY OF ISSAQUAH FOR REVIEW AND APPROVAL PRIOR TO SIGNIFICANT REVISIONS TO TESC MEASURES ARE NEEDED TO ADDRESS PROJECT PHASING OR CHANGED CONDITIONS.
- b. A WET SEASON TESC PLAN IS REQUIRED TO BE SUBMITTED TO DSD FOR APPROVAL TO INITIATE OR CONTINUE CLEARING AND GRADING ACTIVITY DURING OCTOBER 1st THROUGH APRIL 30th, PER IMC 16.26.050. WET SEASON TESC PLAN MUST INCLUDE A DEWATERING PLAN FOR RUNOFF CAPTURE, CONTAINMENT, TURBIDITY MONITORING, AND DISCHARGE OR DISPOSAL METHOD.
- c. FAILURE TO PROVIDE AND MAINTAIN APPROVED TESC FACILITIES AT CONSTRUCTION SITES IS CONSIDERED A VIOLATION OF THE PERMIT AND IS SUBJECT TO STOP WORK AND CODE VIOLATION PENALTIES. 6. OTHER POLLUTION CONTROL MEASURES
- a. THE CONTRACTOR SHALL USE THE APPROPRIATE POLLUTION CONTROL MEASURES TO ENSURE THAT NO LIQUID PRODUCTS OR CONTAMINATED WATER (SUCH AS RUNOFF FROM CONCRETE SLURRY) ENTERS THE STORM DRAINAGE SYSTEM, SURFACE WATERS, OR OTHERWISE LEAVES THE PROJECT SITE.

## 7. RECORD DRAWINGS

- 7.1. CONTRACTORS SHALL MAINTAIN HAND DRAWN RED-LINES, FIELD NOTES AND PHOTOGRAPHS ("FIELD DOCUMENTATION") OF ALL IMPROVEMENTS AS THE WORK PROGRESSES. CONTRACTOR'S FIELD DOCUMENTATION SHALL BE MAINTAINED ONSITE AND SHALL BE AVAILABLE AT ALL TIMES FOR DSD REVIEW. THE DSD INSPECTOR WILL PERIODICALLY REVIEW THE CONTRACTOR'S FIELD DOCUMENTATION AND WILL STOP WORK IF THE CONTRACTOR IS NOT MAINTAINING ADEQUATE RECORDS.
- 7.2. CONTRACTORS SHALL CONTRACT WITH A PROFESSIONAL SURVEYOR LICENSED IN THE STATE OF WASHINGTON TO ACQUIRE ALL THE FIELD DATA REQUIRED TO CREATE THE RECORD DRAWINGS. THE CONTRACTOR'S SURVEYOR SHALL BE THE SURVEYOR OF RECORD FOR THE RECORD DRAWINGS. ALL FIELD LOCATIONS SHALL BE TIED TO AN EASILY MEASURED OBJECT IN THE FIELD SUCH AS LIGHT POLE, MANHOLE, CATCH BASIN, CURB HUB,
- 7.3. DEVELOPER SHALL CONTRACT WITH A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF WASHINGTON TO PREPARE THE RECORD DRAWINGS. THE RECORD DRAWINGS SHALL FOLLOW THE SAME GENERAL FORMAT AS THE APPROVED CONSTRUCTION DRAWINGS AND THEY SHALL CONSIST OF A CLEAN SET OF MYLAR PRINTS WITH ALL CONSTRUCTION NOTES REMOVED AND NO CROSS-OUTS. RECORD DRAWINGS SHALL BE GENERATED USING THE FOLLOWING INFORMATION:
- 7.3.1. CONTRACTOR SUPPLIED SURVEY INFORMATION
- 7.3.2. CONTRACTOR'S FIELD DOCUMENTATION.
- 7.3.3. ENGINEER'S FIELD DOCUMENTATION. 7.3.4. DSD INSPECTOR'S FIELD DOCUMENTATION.
- 7.3.5. FIELD CHANGES AND DESIGN CHANGES.
- 7.3.6. THE APPROVED CONSTRUCTION DRAWINGS.

- 7.4 EACH SHEET OF THE RECORD DRAWINGS SHALL INCLUDE THE FOLLOWING STATEMENTS AND SHALL BE STAMPED AND SIGNED BY THE ENGINEER OF RECORD AND THE SURVEYOR OF RECORD:
- 7.4.1 THE SURVEYOR OF RECORD SHALL SIGN THE FOLLOWING STATEMENT ON EACH SHEET OF THE RECORD DRAWINGS (THE SURVEYOR OF RECORD) HEREBY CERTIFY THAT THE SURVEY INFORMATION SHOWN ON THESE RECORD DRAWINGS ACCURATELY REFLECTS THE FIELD CONDITIONS AS OF \_\_\_\_\_\_
- 7.4.2 THE ENGINEER OF RECORD SHALL SIGN THE FOLLOWING STATEMENT ON EACH SHEET OF THE RECORD DRAWINGS: I \_\_\_\_\_\_ (THE ENGINEER OF RECORD) HEREBY CERTIFY THAT THE FACILITIES SHOWN ON THESE RECORD DRAWINGS MEET THE INTENT OF THE DESIGN.
  - THE INFORMATION SHOWN ON THESE RECORD DRAWINGS WAS COMPILED FROM THE FOLLOWING SOURCES: 1) SURVEY OF VISIBLE FEATURES. 2) CONTRACTOR NOTES, REDLINES AND SURVEY DATA, 3) DSD INSPECTOR COMMENTS, AND 4) APPROVED CONSTRUCTION PLANS. THE ENGINEER OF RECORD CERTIFYING THESE RECORD DRAWINGS HAS NOT WITNESSED ALL ELEMENT OF CONSTRUCTION AND IS NOT RESPONSIBLE FOR ERRORS OR OMISSIONS IN DATA PROVIDED BY THE CONTRACTOR, THE DSD OR THE SURVEYOR OF RECORD.
- 7.5 SANITARY SEWER RECORD DRAWINGS SHALL INCLUDE THE FOLLOWING INFORMATION PLUS ANY ADDITIONAL INFORMATION THAT, BASED ON GOOD ENGINEERING PRACTICES AND THE SPECIFIC PROJECT FEATURES, THE ENGINEER OF RECORD FEELS IS WARRANTED:
- 7.5.1 SEWER PIPELINE PLAN AND PROFILES WITH PIPE MATERIAL, SIZE, LOCATION, SLOPE, AND LENGTH.
- 7.5.2 MANHOLE TYPE, SIZE, LOCATION, RIM ELEVATION, INVERT ELEVATIONS, AND DROP STRUCTURES FEATURES.
- 7.5.3 SIDE SEWER MATERIAL, SIZE, LOCATION, AND INVERT ELEVATION.
- 7.6 WATER RECORD DRAWINGS SHALL INCLUDE THE FOLLOWING INFORMATION PLUS ANY ADDITIONAL INFORMATION THAT. BASED ON GOOD ENGINEERING PRACTICES AND THE SPECIFIC PROJECT FEATURES, THE ENGINEER OF RECORD FEELS IS WARRANTED:
- 7.6.1 WATER PIPELINE PLAN WITH PIPE MATERIAL, SIZE, LOCATION AND LENGTH.
- 7.6.2 WATER VALVE TYPE, MANUFACTURE DATE, SIZE, INVERT ELEVATION AND LOCATION.
- 7.6.3 WATER FITTING TYPE, SIZE, INVERT ELEVATION, BLOCKING DIMENSION AND LOCATION. 7.6.4 WATER MAIN INVERT ELEVATIONS AT 50' SPACING FOR ALL PIPE INSTALLED AT A DEPTH GREATER THAN 5
- 7.6.5 TYPE AND LOCATION OF THRUST RESTRAIN SYSTEM. 7.6.6 FIRE HYDRANT LOCATION.
- 7.6.7 BLOW-OFF SIZE AND LOCATION.
- 7.6.8 AIR & VACUUM RELIEF VALVE SIZE AND LOCATION
- 7.6.9 WATER METER SIZE AND LOCATION.
- 7.7 STORM RECORD DRAWINGS SHALL INCLUDE THE FOLLOWING INFORMATION PLUS ANY ADDITIONAL INFORMATION THAT, BASED ON GOOD ENGINEERING PRACTICES AND THE SPECIFIC PROJECT FEATURES, THE ENGINEER OF RECORD FEELS IS WARRANTED:
- 7.7.1 STORM PIPELINE PLAN AND PROFILES WITH PIPE MATERIAL, SIZE, LOCATION, SLOPE, AND LENGTH.
- 7.7.2 CATCH BASIN TYPE, SIZE, LOCATION, RIM ELEVATION, AND INVERT ELEVATIONS.
- 7.7.3 FLOW CONTROL STRUCTURE TYPE, SIZE, LOCATION, RIM ELEVATION, ORIFICE SIZE, OVERFLOW ELEVATIONS, ETC 7.7.4 LOT DRAIN SIZE, LOCATION AND INVERT ELEVATION.
- 7.7.5 FLOW CONTROL AND WATER QUALITY TREATMENT SYSTEM PLAN AND PROFILES WITH VOLUME, OPERATING LEVELS, OVERFLOW ELEVATIONS, AND OTHER PERTINENT ENGINEERING AND OPERATIONAL FEATURES AND COMPONENTS.
- 7.8 ROADWAY RECORD DRAWINGS SHALL INCLUDE THE FOLLOWING INFORMATION PLUS ANY ADDITIONAL INFORMATION THAT, BASED ON GOOD ENGINEERING PRACTICES AND THE SPECIFIC PROJECT FEATURES, THE ENGINEER OF RECORD FEELS IS WARRANTED:
- 7.8.1 CENTERLINE PROFILE WITH ELEVATIONS AT INTERSECTIONS, PVI'S, BVC'S, AND EVC'S, INCLUDE VERTICAL CURVE DATA.
- 7.8.2 GUTTER LINE ELEVATIONS AT 1/4 POINTS OF INTERSECTION RADIUS RETURNS, INCLUDE CURVE DATA, AND AT ROADWAY WIDTH TRANSITION
- 7.8.3 CHANNELIZATION TYPE AND LOCATION. 7.8.4 SIGNAGE TYPE AND LOCATION.
- 7.8.5 ILLUMINATION TYPE AND LOCATION.
- 7.8.6 RIGHT-OF-WAY MONUMENTATION

#### 8. SITE SAFETY

8.1. CONTRACTORS SHALL COMPLY WITH ALL APPLICABLE LOCAL, STATE AND FEDERAL AGENCY SAFETY STANDARDS.

#### 9. LANDSCAPING

- 9.1. LANDSCAPING REVIEW IN RIGHT-OF-WAY (ROW) IS LIMITED TO UTILITY CONFLICTS AND TREES IN ACCORDANCE WITH THE MASTER STREET TREE PLAN OR OTHERWISE APPROVED BY DSD, COMPLIANCE WITH CONDITIONS IN THE LAND USE PERMIT, DEVELOPMENT AGREEMENT IF APPLICABLE, SITE DISTANCE VISIBILITY, AND CONSISTENCY WITH NEIGHBORHOOD TYPE IN DESIGN GUIDELINES (LANDSCAPING TO COMPLEMENT NEIGHBORHOOD). THE SAME
- APPLIES TO MINI PARKS, UNLESS PLAY EQUIPMENT IS INVOLVED WHICH WOULD BE REVIEWED FOR SAFETY. 9.2. INCLUDE ABOVEGROUND UTILITIES (I.E. LIGHT POLES, HYDRANTS, STREET SIGNAGE, ETC.) ON ALL PLAN SUBMITTALS. PLACE THE FOLLOWING NOTES ON ALL LANDSCAPE PLANS SUBMITTED FOR ISSAQUAH:
- 9.2.1. CONTRACTOR IS RESPONSIBLE FOR VERIFYING THE LOCATIONS OF ALL UNDERGROUND UTILITIES PRIOR TO COMMENCEMENT OF WORK; AND TO
- PROTECT SAID UTILITIES FROM DAMAGE DURING PLANT INSTALLATION. 9.2.2. CONTRACTOR SHALL OBTAIN AND PAY FOR ALL NECESSARY PERMITS AND FEES AS REQUIRED BY APPLICABLE CODES AND ORDINANCES FOR THIS
- 9.2.3. CONTRACTOR SHALL PROVIDE PROTECTION OF ALL PROPERTY, PERSONS, WORK IN PROGRESS, STRUCTURES, UTILITIES, WALKS, CURBS AND PAVED SURFACES DURING THE INSTALLATION OF LANDSCAPE AND IRRIGATION WORK. 9.2.4. CONTRACTOR SHALL KEEP ALL AREAS OF WORK CLEAN, NEAT AND ORDERLY AT ALL TIMES. ALL PAVED AREAS ARE TO BE CLEANED FOLLOWING
- PLANTING AND MAINTENANCE ACTIVITIES. 9.2.5. CONFLICTS BETWEEN APPROVED PLANTING PLANS, LANDSCAPE PERFORMANCE STANDARDS AND EXISTING FIELD CONDITIONS SHALL BE IDENTIFIED TO THE RESPONSIBLE OFFICIAL PRIOR TO PLANTING. 9.2.6. PROPOSALS FOR PLANT SUBSTITUTIONS, LOCATION ADJUSTMENTS, SOIL AMENDMENTS OR ANY VARIATIONS FROM THE APPROVED PLANS SHALL
- REQUIRE PRIOR APPROVAL BY THE RESPONSIBLE OFFICIAL. 9.2.7. SOILS LOCATED IN PLANTING AREAS THAT HAVE BEEN COMPACTED TO A DENSITY GREATER THAN THAT PENETRABLE WITH A HAND SHOVEL (APPROX. 85%), SHALL BE LOOSENED TO INCREASE AERATION FOR A MINIMUM DEPTH OF 18 INCHES FOR THE ENTIRE AREA OF THE COMPACTED SOILS UTILIZED FOR LANDSCAPE PURPOSES. IMPORTED TOPSOIL SHALL BE INCORPORATED INTO LOOSENED SUB GRADE TO A
- MINIMUM DEPTH OF 6. 9.2.8. VERIFICATION OF THE NEED FOR ADDITIONAL SOIL AMENDMENTS WILL BE MADE AT THAT TIME. RECOMMENDED AMENDMENTS SHALL BE APPLIED PRIOR TO PLANTING.
- 9.2.9. USE OF FERTILIZER, ORGANIC OR SYNTHETIC SLOW-RELEASE TYPE, AND PESTICIDES OF ANY KIND SHALL ONLY BE PERMITTED BY THE RESPONSIBLE OFFICIAL. PERMITTED APPLICATIONS OF PESTICIDES SHALL BE APPLIED BY LICENSED APPLICATORS ONLY. ALL USE OF FERTILIZERS, PESTICIDES, AND HERBICIDES SHALL COMPLY WITH BEST MANAGEMENT PRACTICES. APPLICATIONS OF ALL PESTICIDES, HERBICIDES, AND FERTILIZERS SHALL BE MADE IN A MANNER THAT WILL INHIBIT THEIR ENTRY INTO WATERWAYS, WETLANDS, AND STORM DRAINS.
- 9.2.10. ALL PLANT MATERIAL SHALL MEET CURRENT AMERICAN ASSOCIATION OF NURSERYMAN STANDARDS FOR NURSERY STOCK (ANSI 260.1) REQUIREMENTS. ALLOW 24 HOURS MINIMUM NOTIFICATION FOR INSPECTION REQUEST. PLANT MATERIAL THAT HAS BEEN APPROVED FOR INSTALLATION SHALL BE PLANTED WITHIN 24 HOURS. INSTALLATION SHALL NOT BE CONDUCTED UNDER ADVERSE WEATHER CONDITIONS WITHOUT PRIOR APPROVAL OF THE RESPONSIBLE OFFICIAL. PLANT MATERIAL THAT CANNOT BE PLANTED WITHIN ONE DAY FOLLOWING ARRIVAL SHALL BE HEELED-IN, KEPT MOIST AND PROTECTED AT ALL TIMES FROM EXTREME WEATHER CONDITIONS. PLANTS SHALL BE STORED AT THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
- 9.2.11. TREE PITS SHALL BE A MINIMUM OF TWO TIMES (2X) THE DIAMETER OF THE TREE'S ROOT MASS. ADDITIONAL AERATION MAY BE REQUIRED AS DIRECTED BY THE RESPONSIBLE OFFICIAL. ADD WATER TUBES TO THE TREE PLANTINGS IN PAVED AREAS. 9.2.12. STREET TREES SHALL BE SYMMETRICAL AND UNIFORM IN APPEARANCE, SIZE AND STRUCTURE.
- 9.2.13. STREET TREE AND SHRUB SETBACKS SHALL BE CONSISTENT WITH ADOPTED CITY OF ISSAQUAH STREET STANDARDS, AND MEET THE FOLLOWING GENERAL REQUIREMENTS UNLESS OTHERWISE DIRECTED BY THE RESPONSIBLE OFFICIAL: 9.2.14. TREES WILL NOT BE PLANTED IN LOCATIONS THAT COULD LEAD TO ROOTS DAMAGING SIDEWALKS OR CURBING 9.2.15. TREES WILL NOT BE PLANTED TO OBSTRUCT VEHICULAR LINES-OF-SIGHT AT TRAFFIC INTERSECTIONS AND DRIVEWAYS OR TO OBSTRUCT STREET
- LIGHTING, SIGNAGE OR TO RESULT IN A SAFETY CONCERN. 9.2.16. TURF AREAS SHALL CONSIST OF A LOW WATER USE SEED MIX THAT IS WELL ADAPTED TO THE REGION. SPECIFIC SEED SELECTION SHALL BE
- CHOSEN BASED ON SOILS, MAINTENANCE EXPECTATIONS AND PROPOSED USE OF THE PLANTING AREA. 9.2.17. PLANT MATERIALS SHALL BE GUARANTEED FOR A PERIOD OF TWO YEARS. PLANT MATERIAL THAT HAS LOST MORE THAN 30 PERCENT OF ITS NORMAL FOLIAGE SHALL BE REPLACED AS DIRECTED BY THE RESPONSIBLE OFFICIAL.
- 9.2.18. ALL PLANTING AREAS TO RECEIVE 2" DEPTH APPROVED MULCH. 9.2.19. CONTACT THE FOLLOWING PERSONNEL FOR ASSISTANCE OR INFORMATION: DSD PERMIT CENTER - (425) 837-3100.

# UTILITY NOTE


THE CONTRACTOR SHALL VERIEY THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO ANY CONSTRUCTION. AGENCIES INVOLVED SHALL BE NOTIFIED WITHIN A REASONABLE TIME PRIOR TO THE START OF CONSTRUCTION.

THE TOPOGRAPHIC SURVEY WAS PERFORMED BY LDC. INC. IN MAY 2021. ANY CHANGES TO THE SITE AFTER THIS DATE WILL NOT BE REFLECTED IN THE PLANS. ANY DISCREPANCIES FOUND BETWEEN WHAT IS SHOWN ON THE PLANS AND WHAT IS NOTED IN THE FIELD SHOULD BE BROUGHT IMMEDIATELY TO THE ATTENTION OF THE ENGINEER.



HORTO AND

JOB NUMBER: DRAWING NAME: C21124P-RD-DESIGNER: DRAFTING BY: 6-25-1 AS NOTE JRISDICTION: LIOARRI



KLAND HEIGHTS

S P.

Soft OF WASHINGTON

JOB NUMBER: C21–124
DRAWING NAME: C21124P–MB–F
DESIGNER: TPA
DRAFTING BY: RCF
DATE: 6–25–2
SCALE: AS NOTED
JURISDICTION: ISSAQUA

MB-01
SHEET 1 OF 1